

=====

CONSTRUCTION AGREEMENT ? CONTRACT FOR SERVICES

=====

Contract No. : CHI-2026-MXU-0042

Project Code : LAKEFRONT-MIXED-USE-TOWER

Effective Date : January 15, 2026

Execution Date : February 1, 2026

1. PARTIES

Owner / Client : Lakefront Development Partners, LLC

200 North Michigan Avenue, Suite 3400

Chicago, Illinois 60601

Contact: Sarah Chen, VP Development

General Contractor : Meridian Build Group, Inc.

450 West Madison Street

Chicago, Illinois 60661

Architect of Record: Hartwell & Associates Architects

Structural Engineer: K&R Structural Engineers

2. PROJECT IDENTIFICATION

Project Name : Lakefront Mixed-Use Tower ? Phase 1

Project Type : Mixed-Use Commercial / Residential High-Rise

Location : 1200 South Lakeshore Drive, Chicago, IL 60605

Site Address : Block 14, Lakeshore South Parcel, Cook County

Jurisdiction : City of Chicago, Department of Buildings

Description : New construction of a 42-story mixed-use tower comprising retail podium (Levels 1?3), parking (Levels 4?6), office floors (Levels 7?28), and residential condominiums (Levels 29?42). Total building height approximately 520 feet.

3. CONTRACT SUMMARY

Contract Value : USD \$186,500,000.00 (One Hundred Eighty-Six Million Five Hundred Thousand Dollars)

Contingency Allowance: USD \$9,325,000.00 (5.0% of contract value)

Duration : 28 calendar months from Notice to Proceed

NTP Date : March 1, 2026

Substantial Completion Target: July 1, 2028

Final Completion : August 15, 2028

Square Footage : 1,250,000 gross square feet (GSF)

Rentable Area : 980,000 square feet

Floor Count : 42 occupied floors + 2 mechanical penthouses

Complexity Rating : High (urban infill, deep caisson foundation, curtain wall)

4. SCOPE OF WORK

The Contractor shall provide all labor, materials, equipment, and supervision necessary for complete execution of the Work, including but not limited to:

a) Site mobilization, demolition of existing surface parking, and shoring

b) Deep foundation: 84 drilled caissons, 48-inch diameter, avg depth 95 feet

c) Structural steel frame: approximately 14,200 tons wide-flange and HSS members

d) Post-tensioned concrete decks on composite metal deck (floors 7?42)

e) Curtain wall system: unitized aluminum and low-iron glass facade (285,000 SF)

f) MEP rough-in and fit-out: HVAC, plumbing, fire protection, electrical

g) 18 passenger elevators + 2 freight elevators (Otis Gen3 specification)

h) Interior finishes: lobby, common areas, office shell, residential units (312 units)

i) Site utilities, landscaping, and street improvements per City permit

Exclusions: Owner-furnished equipment (kitchen appliances in residential units), specialty artwork, and tenant improvement allowances above Level 28.

5. KEY MILESTONES & PAYMENT SCHEDULE

Milestone	Target Date	Payment %
-----	-----	-----

Notice to Proceed (NTP)	2026-03-01	?
Mobilization & Site Prep Complete	2026-05-15	5%
Foundation Complete	2026-09-30	12%
Structural Steel Topped Out	2027-04-30	20%
Building Enclosed (Dry-In)	2027-10-15	18%
MEP Rough-In Complete	2028-01-31	15%
Substantial Completion	2028-07-01	20%
Final Completion & Punch List	2028-08-15	10%

6. REGULATORY & PERMIT OBLIGATIONS (CONTRACTOR RESPONSIBILITY)

Contractor shall obtain and maintain:

- Building Permit (City of Chicago DOB)
- Demolition Permit (if applicable)
- Shoring & Excavation Permit
- Crane / Street Closure Permits
- Fire Department Plan Review approval
- EPA Stormwater NPDES compliance (ILR10)
- OSHA compliance program

Owner shall assist with zoning verification (PD-843, B3-5 zoning district).

7. INSURANCE & BONDS

Performance Bond : 100% of contract value (Travelers Surety)
 Payment Bond : 100% of contract value
 General Liability : \$5,000,000 per occurrence
 Builder's Risk : Owner-provided; Contractor named as loss payee

8. SPECIAL CONDITIONS

- Winter weather concrete placement restrictions: November 15 ? March 15
- Union labor required: Chicago Regional Council of Carpenters, IBEW Local 134
- LEED Gold certification target; documentation due at Substantial Completion
- Prevailing wage compliance per Illinois Public Act 102-0001 (private project)

END OF CONTRACT EXTRACT ? FOR CONSTRUCTAIQ AGENT TESTING